

SCALE : N.T.S.



SECTION A-A




OPTIONAL PIPE OPENING DETAIL

SEE NOTE 5


INLET BOX SCHEDULE			
L	W	FABRICATION TOLERANCE	
17⅝" (450)	11⅝" (295)	+1" (25)	*
24" (610)	24" (610)	+1" (25)	*
34" (865)	18" (455)	-1" (25)	
34" (865)	24" (610)	-1" (25)	
48" (1220)	30" (760)	+6" (150)	
48" (1220)	48" (1220)	+6" (150)	
66" (1675)	30" (760)	+6" (150)	
66" (1675)	48" (1220)	+6" (150)	
66" (1675)	66" (1675)	+6" (150)	
72" (1830)	24" (610)	-1" (25)	
72" (1830)	48" (1220)	-1" (25)	
72" (1830)	72" (1830)	-1" (25)	

* - THESE BOXES ARE TO BE USED FOR LAWN INLETS AND ARE NOT INTENDED TO BE USED IN THE TRAVELWAY. THE MAX DEPTH FOR THESE BOXES IS 4' (1220). SEE NOTE 8 FOR REINFORCEMENT.


WALL REINFORCEMENT SCHEDULE		
INTERIOR WALL DIMENSION	AREA OF HORIZONTAL REINFORCEMENT PER FOOT (mm^2)	AREA OF VERTICAL REINFORCEMENT PER FOOT (mm^2)
	IN^2 (mm^2)	IN^2 (mm^2)
LESS THAN 4' (1220)	0.132 (85)	0.132 (85)
4' (1220) TO 4.5' (1370)	0.163 (105)	0.132 (85)
4.5' (1370) TO 5' (1525)	0.198 (128)	0.132 (85)
5' (1525) TO 5.5' (1675)	0.239 (154)	0.132 (85)
5.5' (1675) TO 6' (1830)	0.284 (183)	0.132 (85)




24" (610) x 24" (610) LAWN INLET BOX DETAIL



17⅝" (450) X 11⅝" (295) LAWN INLET BOX DETAIL



SECTION B-B



TOP VIEW

NOTES:

1). INLET BOXES SHALL BE PRECAST OR CAST-IN-PLACE.
2). PIPES SHALL NOT BE INSTALLED THROUGH ANY CORNER OF THE INLET BOX.
3). RISER SECTIONS MAY BE USED FOR DEEP INLET BOXES.
4). PIPES MAY BE INSTALLED NEAR OR THROUGH JOINTS FOR RISER SECTIONS.
5). WHEN THE COVER ABOVE THE PIPE IS LESS THAN 4" (100) TO THE COVER SLAB OR TOP UNIT OPENING, THE PORTION OF BOX WALL ABOVE THE PIPE MAY BE REMOVED AS SHOWN IN THE OPTIONAL PIPE OPENING DETAIL. THE AREA ABOVE THE PIPE SHALL THEN BE FORMED AND FILLED WITH HIGH-STRENGTH, NON-SHRINK GROUT MIXED WITH COARSE AGGREGATE IN A 1:1 RATIO BY WEIGHT.
6). CONCRETE FLOW CHANNEL SHALL BE WARPED FOR POSITIVE DRAINAGE.
7). WHEN INLET BOX IS PRECAST, PIPE OPENING SHALL BE BETWEEN 3" (75) AND 4" (100) LARGER THAN OUTSIDE DIAMETER OF PIPE AND SHALL NOT ENCROACH ON ADJACENT WALL.
8). REINFORCEMENT FOR LAWN INLET BOXES SHALL BE 4" (102) X 4" (102), W4 X W4 (W26 X W26) WELDED WIRE.

DELAWARE
DEPARTMENT OF TRANSPORTATION

INLET BOX DETAILS


STANDARD NO. D-4 (2009) | SHT. 1 OF 1

APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 01/19/2010 (DATE)


RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 01/14/2010 (DATE)

08/19/2009


SCALE : N.T.S.




PLAN



TYPE 1 JOINT DETAIL




TYPE 2 JOINT DETAIL




TYPE 3 JOINT DETAIL

* DIMENSIONS WILL VARY


** JOINT SEALANT AS PER SPECIFICATIONS
ONLY BETWEEN 2 PRECAST UNITS



DOUBLE INLET SECTION



SECTION A-A



SECTION B-B


DELAWARE DEPARTMENT OF TRANSPORTATION	DRAINAGE INLET ASSEMBLY		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)
	STANDARD NO. D-5 (2010)	SHT. 1 OF 9	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)

10/26/2010

DRAINAGE INLET FRAME AND GRATES

SCALE : N.T.S.


TYPE 1




PLAN

SECTION C-C


TYPE 2



PLAN




SECTION D-D




SECTION E-E


TYPE 3



PLAN




SECTION F-F




SECTION G-G


TYPE 4



PLAN




SECTION H-H




SECTION I-I


TYPE 5




PLAN



SECTION J-J




SECTION K-K




DRAINAGE GRATE LABELING EXAMPLE DETAIL


TYPE 6




PLAN



SECTION L-L



SECTION M-M



SECTION B-B

SECTION A-A

DRAINAGE INLET FRAME

THIS FRAME IS TO BE USED WITH TYPES 1 THROUGH 4 GRATES ONLY.

NOTES:

1). THE TYPE 2 DRAINAGE INLET GRATE SHALL NOT BE INSTALLED WHERE BICYCLE TRAFFIC MAY BE PRESENT.

2). THE TOP OF ALL DRAINAGE INLET GRATES SHALL BE LABELED "ONLY RAIN DOWN THE STORM DRAIN". ALSO, DRAINAGE INLET GRATES TYPE 1 AND TYPE 4 SHALL BE LABELED WITH "WATER FLOW" AND AN ARROW INDICATING FLOW DIRECTION AS SHOWN IN THE EXAMPLE DETAIL.

3). THE TYPE 1 DRAINAGE INLET GRATE SHALL BE LABELED WITH "CURBSIDE" AS SHOWN ON THE EXAMPLE DETAIL. ALL LABELING ON THE TYPE 1 SHALL BE ON BOTH TOP AND BOTTOM SIDES DUE TO THE TYPE 1 BEING REVERSIBLE.

4). THE TYPE 5 & 6 FRAME AND GRATE COMBINATIONS ARE TO BE USED IN CONJUNCTION WITH LAWN INLET BOXES ONLY. SEE SCHEDULE ON DETAIL D-4, SHEET 1 OF 1, FOR WHICH BOX SIZES ARE CONSIDERED LAWN INLET BOXES.

5). THE TYPE 6 FRAME AND GRATE COMBINATION SHOWN IS THE NEENAH FOUNDRY FRAME AND GRATE COMBINATION MODEL NF-1878-A5G, AN ACCEPTABLE ALTERNATIVE IS THE EAST JORDAN IRON WORKS FRAME AND GRATE COMBINATION MODEL V-5622.

DELAWARE
DEPARTMENT OF TRANSPORTATION


DRAINAGE INLET FRAME AND GRATES

STANDARD NO. D-5 (2010) | SHT. 2 OF 9


APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)

RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)


SCALE : NTS




TYPE A



TYPE D




TYPE E




S501 BENDING DIAGRAM

S501 IS NOT REQUIRED TO BE ONE CONTINUOUS BAR. IF MORE THAN ONE BAR IS USED, THERE MUST BE A 12" OVERLAP BETWEEN BARS.



TYPE B

SEE CURB OPENING DETAIL ON THIS SHEET




CURB OPENING DETAIL

INLET TOP UNIT APPLICATIONS	
TOP UNIT	CURB
TYPE A	USE IN DRAINAGE SWALE
TYPE B	INTEGRAL PCC CURB & GUTTER, TYPE 1-8 & 3-8, PCC CURB TYPE 1-8
TYPE C	INTEGRAL PCC CURB & GUTTER, TYPES 1-6, 3-6, 1-4, 3-4 , 1-2 AND 3-2 AND PCC CURB TYPE 1-6, 1-4, AND 1-2.
TYPE D	INTEGRAL PCC CURB & GUTTER, TYPE 2
TYPE E	PCC CURB TYPE 2


TYPE C

* - THIS DIMENSION VARIES BASED ON THE HEIGHT OF THE CURB AND GUTTER OR CURB USED:
- INTEGRAL P.C.C. CURB AND GUTTER, TYPES 1-6 AND 3-6 & CURB, TYPE 1-6 - 12" MIN.
- INTEGRAL P.C.C. CURB AND GUTTER, TYPES 1-4 AND 3-4 & CURB, TYPE 1-4 - 10" MIN.
- INTEGRAL P.C.C. CURB AND GUTTER, TYPES 1-2 AND 3-2 & CURB, TYPE 1-2 - 8" MIN.



ISOMETRIC VIEW

TYPE E UNIT SHOWN



ISOMETRIC VIEW

TYPE B TOP UNIT SHOWN WITH INTEGRAL CURB & GUTTER TYPE 3

NOTE: LENGTH OF #4 REBAR SHALL BE THE OUTSIDE OF THE DRAINAGE INLET BOX PLUS 2'-9".

DELAWARE
DEPARTMENT OF TRANSPORTATION

DRAINAGE INLET TOP UNITS


STANDARD NO. D-5 (2012) | SHT. 3 OF 9

APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 01/07/2013 (DATE)


RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/20/2012 (DATE)

12/4/2012


SCALE : N.T.S.




48" (1220) x 30" (760) INLET




48" (1220) x 48" (1220) INLET




66" (1675) x 30" (760) INLET




66" (1675) x 48" (1220) INLET




66" (1675) x 66" (1675) INLET



SECTON B-B
FOR TYPE B TOP UNITS



SECTON B-B
FOR TYPES A, C, D, & E TOP UNITS



SECTION A-A


NOTES :

1). RELOCATE ENCROACHING REINFORCING BARS WHEN USING TYPE B UNIT.
2). COVER SLABS SHALL BE PRECAST AND MUST BE SIZED TO FIT INLET BOX DIMENSIONS.
3). ALL BARS ARE TO BE #5 (#16) SPACED @ 6" (150) UNLESS NOTED OTHERWISE. TOP REINFORCEMENT SHALL BE 0.11 IN^2 (70 mm^2) HORIZONTAL REINFORCEMENT PER FOOT IN BOTH DIRECTIONS.
4). MINIMUM BAR COVER = 1 ½" (38).


* - DIMENSIONS TO MATCH OUTSIDE TO OUTSIDE DIMENSIONS OF BOX.

DELAWARE DEPARTMENT OF TRANSPORTATION	DRAINAGE INLET COVER SLAB DETAILS		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)
	STANDARD NO. D-5 (2010)	SHT. 4 OF 9	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)


SCALE : N.T.S.




72" (1830) x 72" (1830) INLET




72" (1830) x 48" (1220) INLET




72" (1830) x 24" (610) INLET



SECTON B-B
FOR TYPE B TOP UNITS




SECTON B-B
FOR TYPES A, C, D, & E TOP UNITS



SECTION A-A

NOTES :

1). RELOCATE ENCROACHING REINFORCING BARS WHEN USING TYPE B TOP UNIT.
2). COVER SLABS ARE TO BE PRECAST AND MUST BE SIZED TO FIT INLET BOX DIMENSIONS.
3). ALL BARS ARE TO BE #5 (#16) SPACED @ 6" (150) UNLESS NOTED OTHERWISE. TOP REINFORCEMENT SHALL BE 0.11 IN^2 (70 mm^2) MIN. HORIZONAL REINFORCEMENT PER FOOT IN BOTH DIRECTIONS.
4). MINIMUM BAR COVER = 1 1/2" (38).




S502 BENDING DIAGRAM

S502 IS NOT REQUIRED TO BE ONE CONTINUOUS BAR. IF MORE THAN ONE BAR IS USED, THERE MUST BE A 12" (300) OVERLAP BETWEEN BARS.


DELAWARE DEPARTMENT OF TRANSPORTATION	DOUBLE INLET COVER SLAB DETAILS	APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)
	STANDARD NO. D-5 (2010) SHT. 5 OF 9	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)

12/23/2010


SCALE : NTS




TYPE A




TYPE B



TYPE D




TYPE C




TYPE E

TOP UNIT DETAILS


NOTE: SEE DETAIL D-5, SHEET 3 OF 9 FOR INLET TOP UNIT APPLICATIONS.



TOP VIEW



SECTION A-A



SECTION B-B


DRAINAGE INLET DETAILS

NOTE: REFER TO PREVIOUS SHEETS FOR REINFORCING REQUIREMENTS
* - SEE OPTIONAL PIPE OPENING DETAIL ON STANDARD NO. D-4, SHEET 1 OF 1


DELAWARE DEPARTMENT OF TRANSPORTATION	34" x 24" DRAINAGE INLET DETAILS		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 01/07/2013 (DATE)
	STANDARD NO. D-5 (2012)	SHT. 6 OF 9	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/20/2012 (DATE)

12/4/2012


SCALE : N.T.S.




TYPE A



TYPE C




TYPE D




TYPE E


TOP UNIT DETAILS



TOP VIEW




SECTION A-A



SECTION B-B

* - SEE OPTIONAL PIPE OPENING DETAIL ON STANDARD D-4, SHEET 1 OF 1.



S504 BENDING DIAGRAM

S504 IS NOT REQUIRED TO BE ONE CONTINUOUS BAR. IF MORE THAN ONE BAR IS USED, THERE MUST BE A 12" (300) OVERLAP BETWEEN BARS.


NOTES:

1). REFER TO PREVIOUS SHEETS FOR REINFORCEMENT REQUIREMENTS.
2). THE HEIGHT OF THIS INLET IS LIMITED TO 4' (1220) MAXIMUM, THEREFORE STEPS WILL NOT BE REQUIRED AND SHOULD NOT BE INSTALLED ON THIS INLET.
3). REFER TO DETAIL D-5, SHEET 3 OF 9 FOR INLET TOP UNIT APPLICATION.


DELAWARE DEPARTMENT OF TRANSPORTATION	34" (865) x 18" (455) DRAINAGE INLET DETAILS	APPROVED SIGNATURE ON FILE — CHIEF ENGINEER — 12/28/2010 DATE
	STANDARD NO. D-5 (2010) — SHT. 7 OF 9	RECOMMENDED SIGNATURE ON FILE — DESIGN ENGINEER — 12/27/2010 DATE

10/28/2010


SCALE : N.T.S.



SINGLE GRATE SETUP



SUBDIVISION TOP & CONFIGURATION



DOUBLE GRATE SETUP


NOTES:


1). MINIMUM BOX SIZE TO BE 34" (850) x 24" (600).
2). PIPE OPENINGS IN THE FRONT WALL SHALL NOT INTERFERE WITH THE STEPS. THE PIPE SHALL BE SHIFTED HORIZONTALLY TO AVOID THE STEPS. IT MAY BE NECESSARY TO USE A LARGER BOX TO AVOID CONFLICT BETWEEN STEPS AND PIPE OPENING.
3). SEE DETAIL D-5, SHEET 3 OF 9, FOR S501 BAR DIAGRAM.
4). THE REBAR IN THE HEAD IS PREFERRED TO BE 1 CONTINUOUS PIECE, HOWEVER, IF MULTIPLE PIECES ARE TO BE USED, EACH PIECE SHALL OVERLAP BY 12" (300) MINIMUM AND THE FINAL LENGTH OF THE SPLICED REBAR SHALL BE AS NOTED ON THIS DETAIL.

DELAWARE DEPARTMENT OF TRANSPORTATION	DRAINAGE INLET TOP UNIT, TYPE S		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)
	STANDARD NO. D-5 (2010)	SHT. 8 OF 9	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)


12/23/2010

SCALE : N.T.S.






CAST-IN-PLACE BOTTOM
SECTION VIEW




ISOMETRIC VIEW

PLAN VIEW



SECTION A-A



SECTION B-B

NOTES:

1). SEE DETAIL D-4, SHEET 1 OF 1 FOR BOX DETAILS AND NOTES.
2). ALL REINFORCEMENT SHALL HAVE A MINIMUM COVER OF 1 ½" (38) UNLESS NOTED OTHERWISE.
3). PIPE SHALL BE SUPPORTED ON BOTH ENDS DURING THE CONSTRUCTION OF THE BASE.
4). VERTICAL WALL REINFORCEMENT SHALL COMPLY WITH A.S.T.M. A615, 0.12 IN/FT IN EACH DIRECTION, VERTICALLY AND HORIZONTALLY.
5). DOGHOUSE OPENING SHALL BE FILLED WITH HIGH STRENGTH, NON-SHRINK GROUT MIXED WITH COARSE AGGREGATE IN A 1:1 RATION BY WEIGHT.
6). THE TOP OF THE DOGHOUSE OPENING SHALL, IN NO CIRCUMSTANCES, BE LESS THAN 4" (100) FROM THE TOP OF THE BOX.
7). DOGHOUSE OPENING WIDTH SHALL BE BETWEEN 3" (75) AND 4" (100) LARGER THAN THE OUTSIDE DIAMETER OF THE PIPE AND SHALL NOT ENCROACH ON THE ADJACENT WALL.
8). EXISTING PIPE IS TO EITHER BE COMPLETELY REMOVED BY SAWCUTTING AS CLOSE TO THE INSIDE BOX WALL AS POSSIBLE, OR BY REMOVING THE TOP PORTION OF THE PIPE AND USING THE REMAINING PIPE SECTION AS THE BOTTOM OF THE FLOW CHANNEL, AS SHOWN IN SECTION B-B.

DELAWARE
DEPARTMENT OF TRANSPORTATION

DOGHOUSE INLET BOX


STANDARD NO. D-5 (2010) | SHT. 9 OF 9

APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)


RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)

08/08/2010


SCALE : N.T.S.



PLAN




TYPE 1 JOINT DETAIL




TYPE 3 JOINT DETAIL

* DIMENSIONS MAY VARY
** JOINT SEALANT AS PER SPECIFICATIONS ONLY BETWEEN 2 PRECAST UNITS



SECTION A-A

• - SEE OPTIONAL PIPE OPENING DETAIL ON STANDARD D-4, SHEET 1 OF 1.




SECTION B-B

BOX MANHOLE ASSEMBLY


DELAWARE DEPARTMENT OF TRANSPORTATION	MANHOLE DETAILS		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 01/19/2010 (DATE)
	STANDARD NO. D-6 (2009)	SHT. 1 OF 4	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 01/14/2010 (DATE)

10/20/2009

SCALE : N.T.S.



PLAN



SECTION A-A

ROUND MANHOLE ASSEMBLY


NOTE: ROUND MANHOLES SHALL BE CONSTRUCTED IN ACCORDANCE WITH AASHTO M 199.

DELAWARE DEPARTMENT OF TRANSPORTATION	MANHOLE DETAILS	APPROVED Eugene M. Hurlburt CHIEF ENGINEER 6/18/01 DATE
	STANDARD NO. D-6 (2001) SHT. 2 OF 4	RECOMMENDED Michael A. Hyde DESIGN ENGINEER 6/15/01 DATE


06/06/2001

SCALE : N.T.S.


NOTE: TOP UNIT IS TO BE CAST IN PLACE TO GRADE AS SPECIFIED ON PLAN SHEETS OR AS DIRECTED BY ENGINEER.




SECTION A-A




SECTION B-B




SECTION C-C



TOP UNIT



FRAME




COVER


DELAWARE DEPARTMENT OF TRANSPORTATION	MANHOLE DETAILS		APPROVED CHIEF ENGINEER — DATE 6/18/01
	STANDARD NO. D-6 (2001)	SHT. 3 OF 4	RECOMMENDED DESIGN ENGINEER — DATE 6/15/01

05/21/2001


SCALE : N.T.S.




48" (1220) X 30" (760) MANHOLE




48" (1220) X 48" (1220) MANHOLE




66" (1675) x 30" (760) MANHOLE




66" (1675) x 48" (1220) MANHOLE



66" (1675) x 66" (1675) MANHOLE



SECTION A-A



SECTION B-B

BOX MANHOLE COVER SLAB DETAILS

NOTES:


1. COVER SLABS SHALL BE PRE-CAST.
2. ALL BARS SHALL BE #5 (#16) SPACED AT 6" (150) ± UNLESS NOTED OTHERWISE.
3. MINIMUM BAR COVER = 1½" (38).

*- DIMENSIONS TO MATCH OUTSIDE TO OUTSIDE DIMENSIONS OF BOX.


DELAWARE DEPARTMENT OF TRANSPORTATION	MANHOLE DETAILS	APPROVED _____ CHIEF ENGINEER 10/24/07 DATE
	STANDARD NO. D-6 (2007) SHT. 4 OF 4	RECOMMENDED _____ DESIGN ENGINEER 10/23/07 DATE

08/01/2007


SCALE : N.T.S.




PLAN



TYPE 3 JOINT DETAIL



SECTION A-A



SECTION B-B


• - SEE OPTIONAL PIPE OPENING DETAIL ON STANDARD NO. D-4, SHEET 1 OF 1.

JUNCTION BOX ASSEMBLY


DELAWARE DEPARTMENT OF TRANSPORTATION	JUNCTION BOX DETAILS		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 01/19/2010 (DATE)
	STANDARD NO. D-7 (2009)	SHT. 1 OF 2	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 01/14/2010 (DATE)

10/20/2009


SCALE : N.T.S.




48" (1220) x 30" (760)
JUNCTION BOX




48" (1220) x 48" (1220)
JUNCTION BOX




66" (1675) x 30" (760)
JUNCTION BOX




66" (1675) x 48" (1220)
JUNCTION BOX



66" (1675) x 66" (1675)
JUNCTION BOX



SECTION A-A



SECTON B-B

JUNCTION BOX COVER SLAB DETAILS

NOTES:

1. COVER SLABS ARE TO BE PRE-CAST.
2. ALL BARS ARE TO BE #5 (#16) SPACED @ 12" (305) ± UNLESS NOTED OTHERWISE.
3. MINIMUM BAR COVER = $1\frac{1}{2}$" (38).
* - DIMENSIONS TO MATCH OUTSIDE TO OUTSIDE DIMENSIONS OF BOX.

DELAWARE
DEPARTMENT OF TRANSPORTATION

JUNCTION BOX DETAILS


STANDARD NO. D-7 (2007) | SHT. 2 OF 2

APPROVED _____ CHIEF ENGINEER 10/24/07 DATE


RECOMMENDED _____ DESIGN ENGINEER 10/23/07 DATE

08/01/2007

SCALE : N.T.S.



CLASS A BEDDING




CLASS C BEDDING

NOTE:
1). USE CLASS C BEDDING UNLESS OTHERWISE INDICATED.
2). FOR CLASS A BEDDING, IMBED PIPE IN CONCRETE 6" (152) FOR PIPES SMALLER THAN 24" (610) I.D., 10" (255) FOR PIPES 24" (610) TO 60" (1525), AND FOR PIPES LARGER THAN 60" (1525) SEE PROJECT DETAILS.


DELAWARE DEPARTMENT OF TRANSPORTATION	PIPE BEDDING		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/28/2010 (DATE)
	STANDARD NO. D-8 (2010)	SHT. 1 OF 1	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/27/2010 (DATE)

10/25/2010

SCALE : N.T.S.




SECTION VIEW




ISOMETRIC VIEW

UNDERDRAIN OUTLET




FRONT VIEW




TOP VIEW

SLOTTED HEADWALL DETAIL




FRONT VIEW

RODENT SCREEN



SECTION



ELEVATION

PERFORATED PIPE UNDERDRAIN


NOTES:

1). THE PERFORATED PIPE UNDERDRAIN SHALL BE LOCATED AS SHOWN ON THE TYPICAL SECTIONS OF THE CONSTRUCTION PLANS.
2). GEOTEXTILE FILTER FABRIC SHALL BE PLACED ENTIRELY OVER THE TOP OF UNDERDRAIN TRENCH AND LAPPED AS SHOWN.
3). SLOPE OF UNDERDRAINS SHALL MATCH ROADWAY GRADE, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
4). OUTLET PIPE CONFIGURATIONS SHALL USE 45 DEGREE ELBOWS OR SHALL USE STRAIGHT PIPE WITH A MINIMUM RADIUS OF 3' (900) TO DIRECT UNDERDRAIN PIPE INTO SIDE OF DRAINAGE INLET OR TO POSITIVE GRADE. PIPE SHALL ALSO BE NON-PERFORATED AND HAVE A SMOOTH INTERIOR.
5). RODENT SCREEN SHALL SNUGLY FIT THE PROVIDED SLOT WITH THE SCREEN LIP FITTING TIGHT TO THE BOTTOM FLOW LINE.
6). A 4' (1200) FLEXIBLE DELINEATOR SHALL BE FURNISHED AND INSTALLED AT THE DIRECTION OF THE ENGINEER TO MARK THE LOCATION OF THE CONCRETE HEADWALL.
7). WHEN TWO LINES OF PIPE UNDERDRAIN DRAIN TO A LOW POINT, EACH PIPE MUST HAVE ITS OWN OUTLET.
8). PERFORATED PIPE UNDERDRAIN SHALL NOT BE PLACED UNDER GUARDRAIL IN ORDER TO AVOID PUNCTURING.

DELAWARE DEPARTMENT OF TRANSPORTATION	PERFORATED PIPE UNDERDRAIN DETAIL		APPROVED CHIEF ENGINEER — DATE 11/18/08
	STANDARD NO. D-9 (2008)	SHT. 1 OF 1	RECOMMENDED DESIGN ENGINEER — DATE 11/17/08

10/23/2008

SCALE : NTS



SECTION

ELEVATION

NOTE:
THE CONTRACTOR SHALL FURNISH MATERIAL AND PLUG ABANDONED DRAINAGE PIPES WITH CONCRETE AS DIRECTED BY THE ENGINEER.

DELAWARE DEPARTMENT OF TRANSPORTATION	PIPE PLUGGING DETAIL		APPROVED SIGNATURE ON FILE (CHIEF ENGINEER) 12/22/2011 (DATE)
	STANDARD NO. D-10 (2011)	SHT. 1 OF 1	RECOMMENDED SIGNATURE ON FILE (DESIGN ENGINEER) 12/21/2011 (DATE)

04/27/2011